LIFT STATION CHART

NUMBER	DESCRIPTION	SPECIFICATIONS
1	LAKE POINTE LS #1 PH4A	150 GPM
2	LAKE POINTE LS #2 SEC 5	110 GPM
3	LAKE POINTE LS #3 SEC 7	68 GPM
4	LAKE POINTE LS #4 SEC 9	125 GPM
5	LAKE POINTE LS #5 SEC 3 PH2	140 GPM
6	LAKE POINTE LS #6 PH2	325 GPM
7	LAKE POINTE PH4B LS #7	70 GPM
8	LAKE POINTE LS #8 HEB PLAZA	125 GPM
9	LAKE POINTE LS #9 PH1	800 GPM
10	LAKE POINTE LS #10	78 GPM
11	LAKE POINTE LS #11 BEE CAVE PLAZA	65 GPM
12	LAKE POINTE LS #12 SEC 6	50 GPM
14	CCNG REGIONAL LS	
15	CCNG EAST LS	

NUMBER	DESCRIPTION	SPECIFICATIONS
16	FALCON HEAD LS #1	59 GPM
17	FALCON HEAD LS #2	575 GPM
18	CCNG CENTRAL LS LOS ROBLES	220 GPM
19	SPANISH OAKS LS #2	
20	SPANISH OAKS LS #4	
21	SUMMIT 56 L.S.	175 GPM
O-1	BEE CAVE ELEMENTARY SCHOOL LS (WCID 17)	
O-2	FALCON HEAD WEST MAIN LS	500 GPM
O-3	FALCON HEAD WEST LS A	25 GPM
O-4	FALCON HEAD WEST LS B	150 GPM
O-5	FALCON HEAD WEST LS C	50 GPM
O-6	FALCON HEAD WEST LS D	25 GPM
O-7	LTHS 1	
O-8	LTHS 2	

(SCALE IN FEET)

LAKE TRAVIS HIGH SCHOOL CAMPUS
LAKE AUSTIN
LITTLE BARTON/ BARTON CREEK
LIFT STATION
SPILLMAN IRRIGATION PUMP STATIONS
AREA 5
R.M. 620 W.W.L.
AREA 4 (MORNINGSIDE)
77AC-FT EFFLUENT POND
100 AC-FT EFFLUENT POND
W.W.T.P. EXPANSION 250,000 gpd
BOHL'S W.W.T.P. 325,000 gpd
LAKEPOINT W.W.T.P. 675,000 gpd
LAKE POINTE
LAKE HILLS CHURCH
EFFLUENT SUBSURFACE IRRIGATION AREA 43.6 AC.
FALCONHEAD WEST
SPILLMAN EFFLUENT IRRIGATION SYSTEM
EFFLUENT IRRIGATION AREA 200 ACRES 600,000 G.P.D.
SPILLMAN RANCH
LADERA RANCH
HOME DEPOT
AREA 1
620 NON-RES
620 NON-RES
AREA 3
PARK
AREA 2
TOWN CENTER
2244 NON-RES A
2244 NON-RES C
McDONALDS GRINDER APPROX. 25 GPM L.S.
HWY. 71 W.W.L.
SKAGGS
71 NON-RES
ANDERSON
SHOPS @ GALLERIA
HEB 2244 NON-RES B
LIFT STATION MODIFICATIONS & FORCE MAIN
LOS ROBLES
SUMMIT 56 TRACT
AREA 8B
AREA 8A
MOUNTAIN LAUREL
AREA 9B
LTISD TRACT
AREA 6
WEST VILLAGE
LAZY 9 M.U.D.
MASONWOOD
80 AC. EAST OF MASONWOOD
BEE CAVE WEST
AREA 9A
AREA 7
SPRINGCREEK ESTATES
CCNG GOLF COURSE IRRIGATION PUMP STATION
EAST VILLAGE
PRESERVE AT BARTON CREEK
GOLF COURSE EFFLUENT IRRIGATION AREA 150 ACRES 400,000 G.P.D.
150 AC. EAST OF CREEKS EDGE
AREA 10
LITTLE BARTON CREEK W.W.L. EXTENSION
HOMESTEAD
SPANISH OAKS OUTPARCEL
BARTON BLUFFS
SPANISH OAKS
SPANISH OAKS 210 IRRIGATION AREA 51 ACRES

LEGEND:

- EFFLUENT FORCE MAIN
- WASTEWATER FORCE MAIN (L.S. & GRINDERS)
- WASTEWATER GRAVITY LINE
- PROPOSED GRAVITY COLLECTION LINE
- PROPOSED FORCE MAIN
- EXISTING P.U.A. LIFT STATION
- PROPOSED P.U.A. LIFT STATION
- EXISTING LIFT STATION OWNED/OPERATED BY OTHERS
- EFFLUENT IRRIGATION AREAS
- CITY OF BEE CAVE CITY LIMITS
- CITY OF BEE CAVE E.T.J.
- SEPTIC OR NO SERVICE NEEDED
- CONSERVATION OR PARK
- WATERSHED BOUNDARY
- SERVICE AREA BOUNDARY

LEGEND

- EXISTING FACILITES
- PROPOSED FACILITIES

PRELIMINARY DRAWING
FOR PLANNING PURPOSES ONLY

MEC
Murfee Engineering Company | Texas Registered Engineering Firm F-353

WEST TRAVIS COUNTY P.U.A.
DRAFT WASTEWATER SERVICE AREA EXHIBIT

1101 Capital of Texas Highway South, Building D, Suite 110, Austin, Texas 78746, (512) 327-9204

JOB NO. 11-021.10	SCALE: AS NOTED	SHEET:	1 OF 1
DESIGNED BY: GWM		DATE:	7/24/2013
DRAWN BY: RWHRC		DATE:	9/13/2013
FILE/LAYOUT: O:\11\021\10\WW\11021013dgn\WWCM (2)			